

# APPENDIX A

## Of the Owensboro Metropolitan Subdivision Regulations

### THE OWENSBORO METROPOLITAN PUBLIC IMPROVEMENT SPECIFICATIONS

#### August 8, 2002 Edition

This edition of the Public Improvement Specifications replaces previous editions. It includes all text amendments adopted by the Owensboro Metropolitan Planning Commission for Owensboro, Whitesville, and Daviess County, Kentucky, through August 8, 2002.

## 1

### INTRODUCTION

1.0 Purpose .....	1-1
1.1 General .....	1-1
1.2 Definitions .....	1-1
1.3 References .....	1-1
1.4 Interpretation .....	1-1
1.5 Obligation of the Contractor .....	1-1
1.6 Obligation of the Developer .....	1-2
1.7 Plans .....	1-2
1.8 Cooperation .....	1-2
1.9 Defective Materials and Workmanship .....	1-2
1.10 Final Inspection .....	1-2
1.11 Record Drawings .....	1-2
1.12 Existing Utilities .....	1-2
1.13 Permits, Easements, and R.O.W. ....	1-2

## 2

### MATERIALS

2.0 Purpose .....	2-1
2.1 Cement Concrete .....	2-1
2.2 Bituminous Concrete and Tack Coat .....	2-1
2.2.1 Tack Coat .....	2-1
2.3 Aggregates .....	2-1
2.3.1 Aggregate Base Course – Dense Grade Aggregate ..	2-1
2.3.2 Aggregate For Bituminous Bases and Pavements .....	2-1
2.3.2a Coarse Aggregate .....	2-1
2.3.2b Fine Aggregate .....	2-1
2.3.2c Aggregate For Streetbase Stabilization .....	2-1
2.3.3 Aggregate For Bedding .....	2-1
2.4 Geotextile Fabrics Materials .....	2-1
2.4.1 Non-woven Fabrics .....	2-1
2.4.2 Woven Fabrics .....	2-2
2.4.3 Geogrid .....	2-2
2.5 Pipework .....	2-2
2.6 Sanitary Sewers .....	2-2
2.6.1 Clay Pipe and Fittings .....	2-2
2.6.2 Ductile Iron Pipe and Fittings .....	2-2
2.6.3 PVC (Polyvinyl Chloride) Pipe and Fittings .....	2-3
2.7 Force Mains .....	2-3
2.7.1 PVC (Polyvinyl Chloride) Pipe and Fittings .....	2-3
2.8 Drainage Pipe .....	2-4
2.8.1 General .....	2-4
2.8.2 Corrugated Metal Pipe and Pipe Arches .....	2-4

2.8.3 Reinforced Concrete Pipe .....	2-4
2.8.4 Reinforced Elliptical Concrete Pipe .....	2-4
2.8.5 PVC (Polyvinyl Chloride) Pipe and Fittings .....	2-5
2.8.6 Adapters and Couplings .....	2-5
2.8.7 Non-Shear Pipe Couplings .....	2-5
2.9 Manholes .....	2-5
2.9.1 Brick and Block .....	2-5
2.9.2 Manhole Gaskets and Boots .....	2-5
2.9.3 Manhole Sealants .....	2-5
2.9.4 Castings .....	2-5
2.9.5 Precast Concrete Rings .....	2-5
2.9.6 Precast Concrete Cones .....	2-6
2.9.7 Steps .....	2-6
2.10 Grout .....	2-6
2.11 Non-Shrink Grout .....	2-6
2.12 Flowable Fill .....	2-6
2.13 Steel Casing Pipe .....	2-6
2.14 Marking Tape .....	2-6
2.15 Locator Wire and Signs .....	2-6

## 3

### STREETS

3.0 Purpose .....	3-1
3.1 Street Geometrics .....	3-1
3.2 Class of Street .....	3-1
3.2.1 Freeways .....	3-1
3.2.2 Arterials .....	3-1
3.2.3 Collectors .....	3-1
3.2.4 Locals .....	3-1
3.2.4a Continuing Streets .....	3-1
3.2.4b Marginal Access Streets .....	3-1
3.2.41c Loop Streets .....	3-2
3.2.4d Cul-de-sac Streets .....	3-2
3.2.4e Dead-end Streets .....	3-2
3.2.4f Alleys .....	3-2
3.3 Pollution Control .....	3-2
3.3.1 General .....	3-2
3.3.2 Open Burning .....	3-2
3.3.3 Dust/Mud Control .....	3-2
3.3.4 Equipment .....	3-2
3.4 Earthwork .....	3-2
3.4.1 Work Conditions .....	3-2
3.4.2 Embankment Construction Methods .....	3-2
3.4.2a Clearing and Grubbing .....	3-2
3.4.2b Excavation .....	3-3
3.4.2b1 Earth Excavation .....	3-3
3.4.2b2 Solid Rock Excavation .....	3-3
3.4.2b3 Unclassified Excavation .....	3-3
3.4.2b4 Borrow Excavation .....	3-3
3.4.2c Embankment Compaction .....	3-3
3.4.3 Blasting Operations .....	3-3
3.4.4 Grading .....	3-4
3.4.5 Subgrade Preparation .....	3-4
3.4.5a Subgrade Compaction .....	3-4
3.4.5b Stabilizer Stone .....	3-4
3.4.5c Portland Cement Stabilization .....	3-4
3.4.5d Lime Stabilized Roadbeds .....	3-4
3.4.5e Time, Weather, and Traffic .....	3-4
3.5 Base Course for Bituminous Concrete and Cement Concrete Surface .....	3-4
3.5.1 Field Density Tests .....	3-4
3.6 Bituminous Concrete Base and Surface Course .....	3-5
3.6.1 Spreading and Finishing .....	3-5
3.6.2 Compaction .....	3-5
3.6.3 Finished Surface Tolerance .....	3-6

*Continued on next page*

*Continued from previous page*

3.6.4 Minimum Construction Length.....	3-6
3.6.5 Transversal Joints.....	3-6
3.6.6 Weather and Seasonal Limitations.....	3-6
3.6.7 Material Specifications.....	3-6
3.6.7.1 Aggregate.....	3-6
3.6.7.2 Asphalt Material.....	3-6
3.6.7.3 Base Course Mixes.....	3-7
3.6.7.4 Surface Course Mixes.....	3-7
3.6.8 Lift Thickness.....	3-7
3.7 Cement Concrete Pavement.....	3-7
3.7.1 Preparation and Control of Concrete Mixes.....	3-7
3.7.1a Batching.....	3-7
3.7.1b Proportioning.....	3-7
3.7.1c Consistency of Concrete.....	3-7
3.7.1d Air Entrainment.....	3-7
3.7.1e Strength of Concrete.....	3-7
3.7.1f Hauling Equipment.....	3-7
3.7.2 Dense Grade Aggregate Base Preparation.....	3-7
3.7.3 Forming.....	3-8
3.7.4 Concrete Placement.....	3-8
3.7.5 Placement of Reinforcing Steel.....	3-8
3.7.6 Spreading and Vibrating Concrete.....	3-9
3.7.7 Concrete Finishing.....	3-9
3.7.8 Joints.....	3-9
3.7.8a Transverse Contraction Joints.....	3-9
3.7.8b Longitudinal Contraction Joints.....	3-9
3.7.8c Transverse Construction Joints.....	3-9
3.7.8d Longitudinal Construction Joints.....	3-9
3.7.8e Transverse Expansion Joints.....	3-9
3.7.8f Sealing of Expansion Joints.....	3-9
3.7.9 Curing Concrete.....	3-9
3.7.10 Protection From Cold Weather and Rain.....	3-10
3.7.11 Final Surface Testing.....	3-10
Exhibit 3-1: Street Design Standards.....	3-11
Exhibit 3-2: Street Design Standards.....	3-12
Exhibit 3-3: Typical Street Cross Sections.....	3-13
Exhibit 3-4: Classes of Streets (Applications).....	3-14
Exhibit 3-5: Classes of Streets (Cross-Sections).....	3-15
Exhibit 3-6: Intersection Design Standards.....	3-16

## 4

### SIDEWALKS, CURB & GUTTER

4.0 Purpose.....	4-1
4.1 Sidewalks Curb and Gutter.....	4-1
4.2 Concrete Sidewalks.....	4-1
4.2.1 Materials.....	4-1
4.2.2 Construction Methods.....	4-1
4.3 Curb and Gutter.....	4-2
4.3.1 Construction Methods.....	4-2
4.3.2 Subgrade.....	4-2
4.3.3 Forms.....	4-2
4.3.4 Concrete Placement.....	4-2
4.3.5 Concrete Finishing.....	4-2
4.3.6 Protection and Curing.....	4-3
4.4 Ramps for Handicapped.....	4-3
Exhibit 4-1: Curb and Gutter Details.....	4-4
Exhibit 4-2: Handicap Ramp Details.....	4-5
Exhibit 4-3: Handicap Ramp Details.....	4-6

## 5

### SANITARY SEWERS

5.0 Purpose and Design Requirements.....	5-1
5.0.1 Depth.....	5-1
5.0.2 Slope.....	5-1
5.0.3 Sizing.....	5-1
5.0.4 Combined Sewers.....	5-1
5.1 Pipe and Fittings.....	5-1
5.2 Trench Excavation.....	5-1
5.2.1 Drainage of Excavations.....	5-2
5.3 Pipe Bedding.....	5-2
5.3.1 Standard Bedding.....	5-2
5.3.2 Special Subgrade Improvement.....	5-2
5.3.3 Dry Mix Concrete Bedding.....	5-2
5.3.4 Rock Cut Bedding.....	5-2
5.4 Laying Pipe.....	5-2
5.4.1 Line and Grade.....	5-3
5.5 Blasting.....	5-3
5.6 Obstructions.....	5-3
5.7 Shoring, Sheeting and Bracing of Excavations.....	5-3
5.8 Backfilling Pipeline Trenches.....	5-4
5.8.1 Method "A" – Backfilling in Open Terrain.....	5-4
5.8.2 Method "B" – Backfilling Under Sidewalks and Unpaved Driveways.....	5-4
5.8.31 Method "C" – Backfilling Under Streets, Roads and Paved Driveways.....	5-5
5.9 Testing of Lines.....	5-5
5.9.1 Sewage Force Mains.....	5-5
5.9.2 Gravity Sanitary Sewer Lines.....	5-6
5.9.2a Deflection Test.....	5-6
5.9.2b Air Test.....	5-6
5.9.2c Infiltration Test.....	5-6
5.9.2d Vacuum Test.....	5-6
5.9.2e Leakage Test.....	5-6
5.10 Steel Casing Pipe.....	5-6
5.10.1 Jack and Bore Construction.....	5-7
5.11 Marking Tape.....	5-7
5.12 Locator Wire and Markers.....	5-7
5.13 Manholes.....	5-7
5.13.1 Standard Manholes.....	5-8
5.13.2 Shallow Manholes.....	5-8
5.13.3 Manhole Inverts Over Existing Sewers.....	5-8
5.13.4 Manhole Frames and Lids.....	5-8
5.13.5 Watertight Sewer Pipe Connections.....	5-8
5.13.6 Joint Sealants.....	5-8
5.13.7 Manhole Concrete Sealants.....	5-8
5.13.8 Drops Into Standard Manholes.....	5-9
5.14 Building Connections.....	5-9
5.15 Connection To Existing Lines.....	5-9
5.16 Removal and Replacement of Existing Facilities.....	5-10
5.16.1 Sidewalks.....	5-10
5.16.2 Pavement.....	5-10
5.16.3 Curb and Gutter.....	5-10
5.17 Concrete Cradle, Anchors, Caps or Encasement.....	5-10
5.17.1 Concrete Cap.....	5-10
5.17.2 Concrete Encasement.....	5-10
5.18 Safeloading.....	5-10
5.19 Flowable Fill.....	5-10
5.20 Locating Near Water Mains.....	5-11
5.20.1 Horizontal Separation.....	5-11
5.20.2 Crossings.....	5-11
5.21 Basements.....	5-11
5.22 Building Demolition.....	5-11
5.23 Grease Traps/Oil Separators/Monitoring Manholes.....	5-11

*Continued on next page*

**Continued from previous page**

5.24 Future Sewer Connections .....	5-11
5.25 Replacement of Existing Mailboxes, Culverts and Other Such Facilities .....	5-11
5.26 Clean-Up.....	5-11
5.27 Seeding and Sodding.....	5-12
Exhibit 5-1: 4'-0" Dia. Manhole w/ Developed Base Detail ...	5-13
Exhibit 5-2: 4'-0" Diameter Open Bottom Manhole Detail ...	5-14
Exhibit 5-3: 4'-0" Dia. Flanged Base Manhole w/ Invert .....	5-15
Exhibit 5-4: 4' – 10' Diameter Manholes w/ Inverts Detail ...	5-16
Exhibit 5-5: 5' – 10' Dia. Flanged Base Manholes Detail .....	5-17
Exhibit 5-6: Plastic Manhole Steps Detail .....	5-18
Exhibit 5-7: 4' - 12' Diameter Flat Top Slabs Detail .....	5-19
Exhibit 5-8: 4'-0" Diameter Eccentric Conicals Detail.....	5-20
Exhibit 5-9: Grade Ring Detail.....	5-21
Exhibit 5-10: Internal Drop Manhole Detail .....	5-22
Exhibit 5-11: 4'-0" Diameter w/ Precast Drop Detail.....	5-23
Exhibit 5-12: Grease Interceptor Detail.....	5-24
Exhibit 5-13: Pump Station Detail.....	5-25
Exhibit 5-14: Valve Pit Detail .....	5-26
Exhibit 5-15: Air Release Pit Detail.....	5-27
Exhibit 5-16: Trapped Inlet/Manhole Detail.....	5-28

**6**

**FIRE PROTECTION REQUIREMENTS**

6.0 Purpose .....	6-1
6.1 New Residential Subdivision (includes Manufactured Housing Park Complexes & Subd.).....	6-1
6.1.1 Water Supply .....	6-1
6.1.2 Fire Hydrant Installation .....	6-1
6.1.3 Fire Hydrant Type .....	6-1
6.2 Commercial and High Density Residential Development.....	6-2
6.2.1 Water Supply .....	6-2
6.2.2 Fire Hydrant Installation .....	6-2
6.2.3 Fire Hydrant Type .....	6-2
6.3 Administrative Enforcement Procedure .....	6-2
6.3.1 Surety .....	6-2

**7**

**STORM SEWERS**

7.0 Purpose .....	7-1
7.1 Design Requirements.....	7-1
7.2 Pipe and Joints .....	7-1
7.3 Trench Excavation .....	7-1
7.4 Pipe Bedding.....	7-1
7.4.1 Reinforced Concrete Pipe (Normal Bedding).....	7-1
7.4.2 High Density Polyethylene Pipe (Improved Bedding).....	7-1
7.4.3 Polyvinyl Chloride Pipe.....	7-1
7.5 Obstructions.....	7-1
7.6 Shoring, Sheeting and Bracing of Excavation.....	7-1
7.7 Laying of Pipe .....	7-1
7.8 Backfilling Pipeline Trenches.....	7-1
7.9 Concrete Cradle, Anchors or Encasement .....	7-1
7.10 Manholes .....	7-1
7.10.1 Standard Manholes .....	7-1
7.10.2 Shallow Manholes .....	7-2
7.10.3 Special Manholes .....	7-2
7.10.4 Precast Concrete Rings .....	7-2
7.10.5 Precast Concrete Cones .....	7-2
7.10.6 Manhole Steps .....	7-2
7.10.7 Manhole Frames and Covers .....	7-2
7.11 Curb inlets, Grate Inlets, and Headwalls.....	7-2

7.12 Tide Gates .....	7-2
7.13 Water Stops .....	7-2
7.15 Clean-Up.....	7-2

Exhibit 7-1: RCP Bedding Detail.....	7-3
Exhibit 7-2: RCP Bedding Detail.....	7-4
Exhibit 7-3: HDPE Pipe Bedding Detail .....	7-5
Exhibit 7-4: PVC Pipe Bedding Detail.....	7-6
Exhibit 7-5: Inlet Box and Casting Details .....	7-7
Exhibit 7-6: Slope and Flared Headwall (12" – 27") .....	7-8
Exhibit 7-7: Slope and Flared Headwall (30" – 60") .....	7-9
Exhibit 7-8: Boxed Culvert Headwall Detail .....	7-10

**8**

**SURFACE DRAINAGE**

8.0 Purpose .....	8-1
8.1 General .....	8-1
8.2 Drainage Ditches and Channels Design Criteria.....	8-1
8.2.1 Design Criteria .....	8-1
8.2.2 Paved Ditches .....	8-1
8.2.3 Drainage Ditch Slope Protection.....	8-1
8.2.4 Construction Requirements .....	8-2
8.2.4a Stripping.....	8-2
8.2.4b Excavation.....	8-2
8.2.4c Fill and Backfill .....	8-2
8.2.4d Grading .....	8-2
8.3 Storm Water Detention .....	8-2
8.3.1 Storm Water Detention Design Criteria.....	8-2
8.3.2 Flood Plain .....	8-2
8.4 Detention Basins .....	8-2
8.4.1 Detention Basin Design Criteria.....	8-3
8.4.1a Detention Dam .....	8-3
8.4.1b Side Slopes .....	8-3
8.4.1c Basin Floor .....	8-3
8.4.1d Low Flow Outlet.....	8-3
8.4.1e Inlet Structure.....	8-3
8.4.1f Outlet Structure .....	8-3
8.4.1g Energy Dissipators .....	8-3
8.4.1h Spillway .....	8-3
8.4.2 Construction Requirements .....	8-3
8.4.2a Clearing and Grubbing .....	8-4
8.4.2b Stripping.....	8-4
8.4.2c Basin Excavation.....	8-4
8.4.2d Compacted Fills.....	8-4
8.4.3 Typical Design Computations .....	8-4
8.4.4 Detention Basin Maintenance.....	8-4
8.5 Building Drains.....	8-4
8.5.1 Roof Drains .....	8-4
8.5.2 Foundation Drains .....	8-5
8.6 Offsite Drainage Improvements .....	8-5

Exhibit 8-1: Typical Paved Ditch Details .....	8-6
Exhibit 8-2: Typical Paved Ditch Details .....	8-7
Exhibit 8-2: Detention Basin and Storm Channel Details .....	8-8
Exhibit 8-4: Plan View of Trapezoidal Ditch Detention .....	8-9
Exhibit 8-5: Plan View of Residential Type Det. Basin .....	8-10
Exhibit 8-6: Plan View of Permanent Pool Type Ret. Basin .....	8-11
Exhibit 8-7: Trash Structure Details .....	8-12
Exhibit 8-8: Rainfall Intensity Owensboro, Kentucky.....	8-13
Exhibit 8-9: Routing Procedure Storage Curve .....	8-14
Exhibit 8-10: Routing Procedure Inflow-Outflow Curves .....	8-15
Exhibit 8-11: Outlet Rating .....	8-16
Exhibit 8-12: Basin Design Table.....	8-17

## 9

### EXISTING FACILITIES: REMOVAL & REPLACEMENT

9.0 Purpose .....	9-1
9.1 Concrete Sidewalks .....	9-1
9.2 Concrete Pavement .....	9-1
9.3 Bituminous Hwy., Street and Driveway Replacement ....	9-1
9.4 Removing and Replacing Concrete Curb and Gutter.....	9-2
9.5 Removing and Replacing Concrete Driveway Aprons ..	9-2
9.6 Replacement of Existing Mail Boxes, Culverts, Fences and other Such Facilities .....	9-2
Exhibit 9-1: Permanent Street Cut Repair Detail.....	9-3

## 10

### SITE RESTORATION: SEEDING AND SODDING

10.0 Purpose .....	10-1
10.1 General .....	10-1
10.2 Procedures and Products.....	10-1
10.2.1 Permanent Seed Mixtures.....	10-1
10.2.1a Turf Quality Tall Fescue .....	10-1
10.2.1b Kentucky Bluegrass.....	10-1
10.2.1c Kentucky 31 Tall Fescue .....	10-1
10.2.2 Temporary Seed .....	10-1
10.3 Permanent Seeding .....	10-1
10.3.1 Preparing the Seed Bed for Turf and Natural Areas..	10-1
10.3.2 Seeding for Turf .....	10-1
10.3.3 Protection for Turf .....	10-2
10.3.3a Straw Mulch Crimping .....	10-2
10.3.3b Straw Mulch and Netting .....	10-2
10.3.3c Tackifier.....	10-2
10.3.3d Hydromulch.....	10-2
10.3.3e Erosion Control Blankets.....	10-2
10.3.3e1 Straw/Netting Matrix.....	10-2
10.3.3e2 Straw/Coconut/Netting Matrix.....	10-2
10.3.3e3 Coconut/Netting Matrix.....	10-2
10.3.3e4 Wood Fiber/Netting Matrix.....	10-2
10.3.9 Seed-Incorporated Erosion Control Blankets .....	10-3
10.3.10 Stage II Topdressing .....	10-3
10.3.11 Maintenance and Repair .....	10-3
10.4 Sodding.....	10-3
10.4.1 Cutting Sod .....	10-3
10.4.2 Preparation of Sod Bed.....	10-3
10.4.3 Placing Sod.....	10-3
10.4.4 Maintenance and Repair .....	10-3
10.5 Clean-Up.....	10-4
10.5.1 Daily Clean-Up.....	10-4
10.5.2 Final Clean-Up .....	10-4

## 11

### EROSION PREVENTION & SEDIMENT CONTROL

11.0 Purpose .....	11-1
11.1 General.....	11-1
11.2 Erosion and Sediment Control Procedures.....	11-1
11.3 Erosion and Sediment Control Techniques.....	11-1
11.3.1 General Techniques.....	11-1
11.3.2 Sediment Runoff Onto Streets.....	11-1
11.3.3 Drop Inlet Sediment Control .....	11-1
11.3.4 Curb Inlets.....	11-1
11.3.5 Drainage Channels .....	11-2

11.3.6 Sediment Basins .....	11-2
11.3.7 Over Lot Perimeter Sediment Control.....	11-2
11.3.8 Embankments .....	11-2
11.4 Maintenance.....	11-2
11.5 Revisions .....	11-2

Exhibit 11-1: Sediment Pond with Sand Filter Outlet .....	11-3
Exhibit 11-2: Installation of Straw Bale Details.....	11-4
Exhibit 11-3: Drop Inlet Protection Using Silt Fence .....	11-5
Exhibit 11-4: Straw Bale Drop Struct. for Drainage Chan.....	11-6
Exhibit 11-5: Installing a Filter Fabric Silt Fence .....	11-7
Exhibit 11-6: Gravel Filter for Area Inlet.....	11-8
Exhibit 11-7: Curb Inlet Gravel Filter.....	11-9
Exhibit 11-8: Rock Check Dam Details.....	11-10
Exhibit 11-9: Small Sediment Trap w/i Drainage Channel....	11-11

## 12

### STRUCTURES

12.0 Purpose.....	12-1
12.1 Description of Work .....	12-1
12.2 Materials .....	12-1
12.2.1 Concrete .....	12-1
12.2.2 Steel Reinforcement.....	12-1
12.2.3 Grout.....	12-1
12.2.4 Non-Shrink Grout .....	12-1
12.3 Precast Structures.....	12-1
12.3.1 Precast Manhole Sections .....	12-2
12.4 Execution of Work for Connections.....	12-2
12.4.1 Connections .....	12-2
12.4.2 Manholes and Wet-Wells.....	12-2
12.4.3 Small Structures .....	12-3
12.4.4 Concrete Box Culverts, Retaining Walls and Headwalls .....	12-3
12.4.4.1 Footings .....	12-3
12.4.4.2 Culvert Inverts, Aprons, Curtain Walls, and Headwalls .....	12-3
12.4.4.3 Retaining Walls .....	12-4
12.4.4.4 Placing Concrete .....	12-4
12.4.4.5 Placing Fill.....	12-4
12.4.5 Adjusting Manholes, Inlets and Trapped Catch Basins .....	12-4
12.4.6 High-Density Polyethylene (HDPE) Grade Adjustment Rings.....	12-4

## 13

### CONCRETE SPECIFICATIONS: MATERIALS & METHODS

13.0 Purpose.....	13-1
13.1 Description of Work .....	13-1
13.2 Material .....	13-1
13.2.1 Portland Cement Concrete .....	13-1
13.2.1a Portland Cement .....	13-1
13.2.1b Water .....	13-1
13.2.1c Fine Aggregates .....	13-1
13.2.1d Coarse Aggregates.....	13-1
13.2.1e Air-Entraining Admixtures.....	13-1
13.2.1f Chemical Admixtures.....	13-1
13.2.1g Fly Ash.....	13-1
13.2.2 Concrete Reinforcement.....	13-1
13.2.2a Steel Bars.....	13-1
13.2.2b Welded Steel Wire Fabric.....	13-1
13.2.2c Polypropylene Fibers.....	13-1

Continued on next page

**Continued from previous page**

13.2.3 Curing and Finishing Materials ..... 13-1  
 13.2.3a Concrete Curing Materials ..... 13-1  
 13.2.3b Masonry Coating Materials ..... 13-1  
 13.3 Execution of Work ..... 13-2  
 13.3.1 Care, Storage and Handling of Concrete Materials... 13-2  
 13.3.2 Admixtures ..... 13-2  
 13.3.3 Proportioning ..... 13-2  
 13.3.4 Class of Concrete ..... 13-2  
 13.3.4a Class AA Concrete ..... 13-2  
 13.3.4b Class A Concrete ..... 13-2  
 13.3.4c Class B Concrete ..... 13-2  
 13.3.4d Class M Concrete ..... 13-2  
 13.3.4e Class P Concrete ..... 13-2  
 13.3.5 Flowable Fill ..... 13-2  
 13.3.6 Slipform ..... 13-2  
 13.3.7 Batching and Mixing ..... 13-2  
 13.3.7a General ..... 13-2  
 13.3.7b Ready-Mixed Concrete ..... 13-2  
 13.3.7c Hand-Mixed Concrete ..... 13-3  
 13.3.8 Forms ..... 13-3  
 13.3.8a General ..... 13-3  
 13.3.8b Removal of Falsework and Forms ..... 13-4  
 13.3.9 Concrete Reinforcing ..... 13-4  
 13.3.9a Concrete Reinforcing ..... 13-4  
 13.3.9b Bending Steel Reinforcing Bars ..... 13-4  
 13.3.9c Placing and Fastening ..... 13-4  
 13.3.9d Splicing ..... 13-4  
 13.3.9e Fiber Reinforcing ..... 13-5  
 13.3.10 Placing Concrete ..... 13-5  
 13.3.10a General ..... 13-5  
 13.3.10b Weather Limitations and Protection ..... 13-6  
 13.3.11 Curing Concrete ..... 13-6  
 13.3.11a General ..... 13-6  
 13.3.11b Wet Curing ..... 13-6  
 13.3.11c Membrane Curing ..... 13-6  
 13.3.12 Surface Finish ..... 13-7  
 13.3.12a General ..... 13-7  
 13.3.12b Ordinary Surface Finish ..... 13-7  
 13.3.12c Masonry Coating Finish ..... 13-7  
 13.3.12d Floated Surface Finish ..... 13-8  
 13.3.13 Sampling and Testing ..... 13-8  
 13.3.13a Personnel ..... 13-8  
 13.3.13b Sampling Fresh Concrete ..... 13-8  
 13.3.13c Slump Test ..... 13-8  
 13.3.13d Air Content ..... 13-8  
 13.3.13e Test Cylinders ..... 13-8  
 13.3.13f Comprehensive Strength Tests ..... 13-9  
 13.3.13g Frequency of Tests ..... 13-9  
 13.4 Concrete Mix Designs and Placing Methods ..... 13-9  
 13.4.1 Purpose ..... 13-9  
 13.4.2 Practices to Prevent Scaling ..... 13-9  
 13.4.2a Use of Air-Entrained Concrete ..... 13-9  
 13.4.2b Deicing ..... 13-9  
 13.4.2c Curing ..... 13-9  
 13.4.2d Finishing ..... 13-9  
 13.4.2e Winter Work ..... 13-9  
 13.4.3 Practices to Minimize Cracking ..... 13-9  
 13.4.3a Subgrade and Formwork ..... 13-9  
 13.4.3b Concrete ..... 13-9  
 13.4.3c Finishing ..... 13-10  
 13.4.3d Curing ..... 13-10  
 13.4.3e Joints ..... 13-10  
 13.4.3f Cover over Reinforcement ..... 13-10  
 13.4.4 Cold Weather Concreting ..... 13-10

**ACKNOWLEDGMENTS**

Special thanks are given to members of the 2002 Public Improvement Specifications Review Committee. Each member donated a significant amount of time, energy, and resources to the preparation of this document. With the exception of local government and agency staff, members of the committee did not receive compensation for their efforts.

2002 Public Improvement Specifications Review Committee

Tom Allinder, PE/PLS	Johnson, Depp and Quisenberry
George Ballard	Home Builders Association of Owensboro, Contractor Rep.
*Dean Behnke, PE	Regional Water Resource Agency
Don Bryant, PE/PLS	Bryant Engineering, Inc.
*Gary Noffsinger, AICP	Owensboro Metropolitan Planning Commission
Mike O'Bryan	Home Builders Association of Owensboro Representative
Ward Pedley	Home Builders Association of Owensboro Representative
*Marwan Rayan, PE	City of Owensboro Engineer
*Sinan Rayyan, PE	Daviess County Engineer
James Riney, PE/PLS	HRG PLLC Surveying and Engineering

\*Local government or agency staff

The following staff members of the Owensboro Metropolitan Planning Commission (OMPC) or the City of Owensboro Engineering Department also contributed to this report:

- Gary Adams, AICP, OMPC Associate Director of Planning
- Becky Watson, OMPC Planner II
- Doug Fulkerson, Engineering Technician
- Debbie Price, Engineering Technician
- Joe Schepers, Assistant City Of Owensboro Engineer

Historical Background

The following Abstract and Acknowledgments were included in the March 1976 printing of the Public Improvement Specifications.

**ABSTRACT**

TITLE: Public Improvement Specifications of the Owensboro Metropolitan Planning Commission

AUTHOR: G. Reynolds Watkins Consulting Engineers, Inc., Lexington, KY

SUBJECT: Public Improvement Specifications

DATE: June 1975

PLANNING AGENCY: Owensboro Metropolitan Planning Commission

SOURCE OF COPIES: Owensboro Metropolitan Planning Commission  
Fourth and Allen Streets  
Post Office Box 327 Owensboro, Kentucky 42301  
Telephone 502-683-1543

PROJECT NUMBER: 440-01-31

NUMBER OF PAGES: 48

ABSTRACT: This report is intended to serve as the specifications for certain types of public improvements constructed within the area under the jurisdiction of the Owensboro Metropolitan Planning Commission. Included in the specifications~ are the following:

INTRODUCTION - containing general overall requirements.

MATERIALS - provides specs for primary materials used in construction.

STREETS - provides standards for design and construction of streets.

SIDEWALKS, CURB, AND GUTTER - standards for design, construction, and inspection of concrete sidewalks, curb, and gutter.

SANITARY AND STORM SEWERS AND SURFACE DRAINAGE FACILITIES - standards for design and construction.

REMOVAL - standards for removal and replacement of existing facilities.

SEEDING - standards for seeding and sodding.

FEDERAL FINANCIAL ASSISTANCE: The preparation of this report was financed in part through a Comprehensive Planning Grant from the Department of Housing and Urban Development, under the Planning Assistance Program authorized by Section 701 of the Housing Act of 1954, as amended.

**ACKNOWLEDGMENTS**

Daviess County Fiscal Court

Pat Tanner	County Judge
William Froehlich	Commissioner
John W. Oldham	Commissioner
James L. Riney	Commissioner

Owensboro City Commission

Jack Fisher	Mayor
Max Rhoads	City Manager
Robert Maddox	Commissioner
John Medley, Jr	Commissioner
Alton Puckett	Commissioner
Claudia Myles	Commissioner

Whitesville Board of Trustees

Glenn Woods	Mayor
Wanda Brooks	Trustee
C. F. Carter	Trustee
Robert Howard	Trustee
Harold Martin	Trustee

Owensboro Metropolitan Planning Commission

Roger Anderson	Planning Director
Dr. Albert Joslin	Chairman
Col. Willis Brooks	Vice-Chairman
Jarred Barron	Commissioner
Jolly Hayden	Commissioner
Holloway Hawes	Commissioner
Robert Hoskins	Commissioner
Billy Joe Miles	Commissioner
W. M. Norris, Jr.	Commissioner
Lee K. Nelson	Commissioner
Edward Wathen	Commissioner
Charles Kamuf	Attorney

Special thanks is given to Roger Anderson, Director of the Owensboro Metro Planning Commission and William Reynolds, Owensboro City Engineer, for their assistance and kind support.

Staff members of G. Reynolds Watkins Consulting Engineers, Inc., contributing to this report included Ben Fister, P.E.; Dr. Bill Qualls, A.I.P.; Bob Smallwood, BSCE; Kathi Whalen; Charles S. Howlett, BSCE; Norman Hill, Susan Sparks, Terri Holbrook, Joe Anderson, and Karen Lessig.

David Daugherty, P.E. and Consulting Hydrologist, also contributed as a member of the GRW team.

March 1976

# Appendix A

Of The Owensboro Metropolitan Subdivision Regulations

# THE PUBLIC IMPROVEMENT SPECIFICATIONS

**The Owensboro Metropolitan Public Improvement Specifications**

As adopted by the Owensboro Metropolitan Planning Commission

For Owensboro, Whitesville, & Daviess County, KY

